DETAIL PROTECTION AND SURFACING



TRIFLEX CRYL FINISH 202 @ 0.80 Kg/m² MIN.

TRIFLEX DECKFLOOR RS THIXO (BLACK) @ 4.50 Kg/m² MIN. WITH TRIFLEX EMERY (1.0 - 3.0mm) @ 6.00 Kg/m² APPROX.

TRIFLEX PROPARK® @ 3.00 Kg/m² MIN.

TRIFLEX 110g REINFORCEMENT FLEECE

TRIFLEX PROPARK® @ 3.00 Kg/m² MIN.

TRIFLEX 110g REINFORCEMENT FLEECE

TRIFLEX PRIMER (REFER TO PROJECT SPECIFICATION PROPOSAL)

GENERIC DIMENSIONALLY STABLE / SUITABLE SUBSTRATE (PREPARED)

DETAIL PROTECTION AND SURFACING



TRIFLEX CRYL FINISH 202 @ 0.80 Kg/m² MIN.

TRIFLEX DECKFLOOR RS THIXO (BLACK) @ 4.50 Kg/m² MIN. WITH TRIFLEX EMERY (1.0 - 3.0mm) @ 6.00 Kg/m² APPROX.

TRIFLEX PROPARK® @ 3.00 Kg/m² MIN.

TRIFLEX 110g REINFORCEMENT FLEECE

TRIFLEX PRIMER (REFER TO PROJECT SPECIFICATION PROPOSAL)

GENERIC DIMENSIONALLY STABLE / SUITABLE SUBSTRATE (PREPARED)

MAIN AREA WATERPROOFING



TRIFLEX CRYL FINISH 202 @ 0.80 Kg/m² MIN.

TRIFLEX DECKFLOOR RS THIXO (BLACK) @ 4.50 Kg/m² MIN. WITH TRIFLEX EMERY (1.0 - 3.0mm) @ 6.00 Kg/m² APPROX.

TRIFLEX PRIMER (REFER TO PROJECT SPECIFICATION PROPOSAL)

GENERIC DIMENSIONALLY STABLE / SUITABLE SUBSTRATE (PREPARED)

NOTES

1. TRIFLEX CRYL PASTE OR TRIFLEX FLEXFILLER (REFER TO PROJECT SPECIFICATION)
2. SURFACE / REFLECTIVE CRACKING MAY OCCUR IN THE AGGREGATE FILLED FINISH



CAR PARK | MARKINGS | REPAIRS

GENERAL NOTES

This drawing and any reference to structural / thermal elements should be treated as indicative only and read in conjunction with the Triflex Project specification proposal and relevant Triflex technical data. Details should be verified for accuracy and suitability as we specifically exclude any liability for errors, omissions or otherwise.

The drawing should not be reproduced or amended except with the written permission of Triflex. Do not scale, use figured dimensions only, and check all dimensions on site.

INDICATIVE SYSTEM BUILD-UP



SYSTEM

TRIFLEX DECKFLOOR RAMP WITH EMERY 1.0 - 3.0mm

PROJECT

STANDARD

DETAIL

OVERBANDING CRACK GREATER THAN 0.5mm _CONCRETE

DRAWING NUMBER

DECKFLOOR RAMP_071 _OVERBANDING CRACK GREATER THAN 0.5mm _CONCRETE

SCALE	DATE
NTS	13/08/2018

Triflex

Delivering solutions together

Triflex (UK) Limited

Whitebridge Way | Stone | Staffs
ST15 8JS | Tel: 01785 819119
www.triflex.co.uk | info@triflex.co.uk